

DEPARTMENT OF ADMINISTRATION

DIPATTAMENTON ATMENESTRASION

DIRECTOR'S OFFICE (Ufisinan Direktot) Telephone (Telifon): (671) 475-1101/1250



May 4, 2023

Invitation For Bid
GSA-032-23
Purchase and Install two (2) each 10 Ton Package Air Conditioning Units

AMENDMENT #2

- 1.) Amend to replace page 33 of 33 with the "Revised 05/04/2023 Page 33 of 33," attached.
- 2.) Amend page 3 of 33.

From:

This bid shall be submitted in duplicate and sealed to the issuing office above no later than (Time) 10:00am, Date: 05/05/2023 and shall be publicly opened. Bid submitted after the time and date specified above shall be rejected. See attached General Terms and Conditions, and Sealed Bid Solicitation for details.

To now read:

This bid shall be submitted in duplicate and sealed to the issuing office above no later than (Time) 10:00am, Date: 05/15/2023 and shall be publicly opened. Bid submitted after the time and date specified above shall be rejected. See attached General Terms and Conditions, and Sealed Bid Solicitation for details.

All others remain unchanged.

Please Note: Follow up/Clarification to the Questions and Concerns responses dated 05/04/2023 must be submitted to the General Services Agency via fax (671-472-4271) and email to gsaprocurement@gsadoa.guam.gov no later than 5pm, Friday, May 5, 2023.

CLAUDIA S. RAY
Chief Procurement Officer

Please Print Acknowledgement Copy (Re-Fax to GSA)					
Received By:					
Date					
Company Name:					
Fax to: 475-1727 or 472-4217					
Email to: esaprocurement@esadoa.enam.eov					

ITEM NO.	DESCRIPTION	QTY	UOM	UNIT PRICE	PRICE EXTENSION	
1.1	Cost to Replace two (2) each, 10 Ton package type air conditioning units for DYA Echo Unit, North and Foxtrot Unit, General Population located at 169 San Isidro St., Mangilao, Guam 96913 to include Shipping handling, delivery, installation and testing.	2	ea.	\$	\$	
SPEC	IFICATIONS:			BIDDING	ON/REMARKS	
-	Installation of new 10-ton package type, 208-230v / 3phase / 60	hz units				
-	10-Ton Package units should have copper tubing and aluminum Anti-corrosion spray.					
-	Remove and replace supply and return transition duct connection to existing supply/return with internal insulation, using prime grade galvanized sheet metals					
-	Provide necessary flexible connectors, sealant and support for the	ne ducts				
-	Secure unit at its existing base using angle bracket and threaded rods					
-	Supply and install drain lines			······		
-	Provide and install electrical power connection to terminate to existing power supply disconnects					
-	Provide anti-corrosion Heresite phenolic coating for the condens included with the units					
-	Outdoor unit should have equivalent rating of voltage monitor device for power fluctuation, if the unit does not include a built-in device					
-	Reconnect all existing UV ducts					
-	Remove and recycle refrigerants from existing units into new un to be in accordance with EPA regulations	nits				
-	Removal and transportation of old A/C unit from existing location to DYA Maintenance office near Bldg. C					
-	Removal of associated project debris					
-	Start-up testing and commissioning of unit					
175	With three-year warranty and service coverage					
Biddin	g On:					
Make:_	acturer:					
Place of Date of	f Origin: Delivery:					

These specifications were prepared by Don Taitingfong, Maintenance Leader, and approved by Melanie Brennan, Director of the Department of Youth Affairs.