



EDWARD M. BIRN
Director (Direktot)
ELIZABETH T. FISHER
Deputy Director (Sigundo Direktot)

**DEPARTMENT OF
ADMINISTRATION**
DIPATTAMENTON ATMENESTRASION
DIRECTOR'S OFFICE
(Ufisinan Direktot)
Telephone (Telifon): (671) 475-1101/1250



LOURDES A. LEON GUERRERO
Governor (Maga'håga)
JOSHUA F. TENORIO
Lt. Governor (Sigundo Maga'låhi)

May 8, 2023

Invitation For Bid
GSA-032-23

Purchase and Install two (2) each 10 Ton Package Air Conditioning Units

AMENDMENT #3

1.) Amend to replace page 33 of 33 with the "Revised 05/08/2023 Page 33 of 33," attached.

All others remain unchanged.

For [Signature]

CLAUDIA S. RAY
Chief Procurement Officer

Please Print
Acknowledgement Copy (Re-Fax to GSA)

Received By: _____
Date: _____
Company Name: _____
Fax to: 475-1727 or 472-4217
Email to: gsa procurement@gsadna.guam.gov

ITEM NO.	DESCRIPTION	QTY	UOM	UNIT PRICE	PRICE EXTENSION
1.1	Cost to Replace two (2) each, 10 Ton package type air conditioning units for DYA Echo Unit, North and Foxtrot Unit, General Population located at 169 San Isidro St., Mangilao, Guam 96913 to include Shipping handling, delivery, installation and testing.	2	ea.	\$ _____	\$ _____

SPECIFICATIONS:

- Installation of new 10-ton package type, 208-230v / 3phase / 60hz units
- 10-Ton Package units should have copper tubing and aluminum fins with Anti-corrosion spray.
- Remove and replace supply and return transition duct connection to existing supply/return with internal insulation, using prime grade galvanized sheet metals
- Provide necessary flexible connectors, sealant and support for the ducts
- Secure unit at its existing base using angle bracket and threaded rods
- Supply and install drain lines
- Provide and install electrical power connection to terminate to existing power supply disconnects
- Provide anti-corrosion Heresite phenolic coating for the condenser coil, if not included with the units
- Outdoor unit should have equivalent rating of voltage monitor device for power fluctuation, if the unit does not include a built-in device
- Reconnect all existing UV ducts
- Remove and recycle refrigerants from existing units into new units to be in accordance with EPA regulations
- Removal and transportation of old A/C unit from existing location to DYA Maintenance office near Bldg. C
- Removal of associated project debris
- Start-up testing and commissioning of unit
- With five-year warranty and service coverage

BIDDING ON/REMARKS

Bidding On:

Manufacturer: _____

Make: _____

Year: _____

Place of Origin: _____